



- NOTES:

 1. PRECAST CONCRETE f'c x 5000 PSI @ 28 DAYS

 2. REINFORCEMENT SHALL CONFORM TO ASTM C-478

 3. CAST LIFT LUGS ARE REQUIRED FOR 4" AND 6" RINGS.

 4. INSTALL MORTAR NOT LESS THAN 1/4 INCH THICK BETWEEN RINGS.RED FOR 4" AND 6" RINGS.

CHARLES COUNTY GOVERNMENT	STANDARD DETAIL	REVISIONS:	
DEPARTMENT OF PLANNING & GROWTH MANAGEMENT APPROVED: DIRECTOR OF DEVELOPMENT SERVICES DATE WATER / SEWER ENGINEER DATE	24" PRECAST CONC. MANHOLE ADJUSTING GRADE RING		S 3.06